

Page Denied

~~TOP SECRET~~

Copy 5
3 Pages

12666
NPIC/R-268/64
May 1964

PHOTOGRAPHIC INTERPRETATION REPORT

PETROVKA SHIPYARD PETROVKA, USSR

Declass Review, NIMA/DoD



CIA




DIA



25X1

NATIONAL PHOTOGRAPHIC INTERPRETATION CENTER



~~TOP SECRET~~

GROUP 1
Excluded from automatic
downgrading and declassification

TOP SECRET

25X1

NPIC/R-268/64

25X1

PETROVKA SHIPYARD PETROVKA, USSR

Petrovka Shipyard [] is located on a small bay on the east shore of Ussuriyskiy Bay, 2.7 nautical miles (nm) south-

west of Petrovka, immediately northwest of Bolshoy Kamen and 20 nm east of Vladivostok at 43-07N 132-20E (Figure 1).




FIGURE 1. GENERAL LOCATION MAP.

FACILITIES

25X1

25X1

Facilities at the shipyard (Figure 2) include five piers, a mole, shop buildings, cranes, a probable transverser, probable shipways, a wet dock, a stores area, an area under construction, housing, support and storage areas. The installation is rail and road served.

Operations Area. The five piers are road served. Piers I, II and III are probably of heavy construction to support fitting out operations. They are 780 by 45 feet, [] and 375

by [] feet respectively. Piers IV and V are 220 by [] feet and [] feet. Approximately 1,650 feet of quayed shoreline exists in this area. A floating dock/transporter [] is usually mediterranean moored in the dock between piers I and II. The 510- by 265-foot mole appears to be rock-filled behind bulkheads. It supports two buildings 270 by 35 feet and 140 by 45 feet. The wet dock is 450 by 320 feet inside (550 by 400 feet overall) with a 55-foot wide entrance. A probable [] trans-

- 1 -

25X1

25X1

TOP SECRET

25X1

25X1

TOP SECRET

25X1

NPIC R-268 64




FIGURE 2. PETROVKA SHIPYARD, USSR.

- 2 -

TOP SECRET

25X1

TOP SECRET

25X1

25X1

25X1

NPIC /R-268 /64

25X1

25X1

verser with 580 feet of travel is located directly southeast of the wet dock and directly in line with three probable shipways 575 feet long separated in the center by [redacted]. A bridge crane way 185 feet wide by 460 feet long parallels the shipways. Seven large shop buildings, 330 by 190 feet, 550 by 180 feet, [redacted] feet, 295 by 315 feet, 247 by 170 feet, 205 by 80 feet and [redacted] feet are located southeast of the piers. A [redacted] thermal power plant and a walled storage area containing two buildings, [redacted] ft, are located near the south edge of the area. Fifteen storage, support buildings with 69,500 square feet of floor space and 11 small miscellaneous buildings are located in this area.

Stores Area. Open storage and construction activity dominate this area, which is rail served. Facilities consist of two quays, 320 by 300 feet long, the latter supporting a T-head crane, 22 storage/support-type buildings with 161,700 square feet of floor space, two miscellaneous small buildings and a walled open storage area.

Construction Area. Facilities in the construction area consist of two large bulk-headed fill areas containing three probable shop buildings 240 by 220, 240 by 55 and 170 by 40 feet,

eight storage buildings with approximately 50,000 square feet of floor space, one 115- by 75-foot administration/housing building and 10 miscellaneous small buildings. Two road-served underground entrances are located on the north shore of the Bay.

Housing Area. Facilities in the housing area consist of 26 four-story barracks with 1,195,700 square feet of floor space, 72 two-story multiple dwelling units with approximately 1,426,000 square feet, an administration-type building with 44,500 square feet, nine single dwellings with 13,700 square feet, five storage-type buildings with 29,200 square feet and 18 small miscellaneous buildings.

Support Area. Facilities in the support area consist of 16 storage-type buildings with 125,600 square feet of floor space, a secured storage building with 7,450 square feet, a walled area containing an administration-type complex building with 21,000 square feet and two small miscellaneous buildings.

Storage Area. Facilities in the storage area consist of 65 storage buildings with 495,400 square feet of storage space and nine miscellaneous small buildings.

REFERENCES

25X1

MAPS OR CHARTS

ACIC. US Air Target Chart Series 200. Sheet 0291-6HL. 3d ed. Jan 63. Scale 1:200,000 (SECRET)

REQUIREMENT

C-14-81,001 (partial answer)

NPIC PROJECT

N-119 /64

- 3 -

TOP SECRET

25X1